

Subject: Fwd: PROPOSAL (new) SOLUGH WALL
From: Donald Duckworth <duckworth.donald@gmail.com>
Date: 06/04/2015 06:08 AM
To: Fred Sutton <Fred.Sutton@lacity.org>
CC: John Ruhlen <jruhlen916@aol.com>, Miki Payne2 <miki@hbdrollinger.com>
BCC: Donald R Duckworth <duckworth.donald@gmail.com>, Jack Davis <jsdla@aol.com>

Good Morning Fred...

I forgot all about this last week! Here is the east side (SRS) slough wall proposal. Adding a reasonable contingency, because there will be costs that were not anticipated, this contractor's cost should be considered to be \$12,000.00.

What's the next step here?

Thanks for your help.

----- Forwarded message -----
From: <DERRYLDENNE@aol.com>
Date: Tue, Mar 24, 2015 at 11:22 AM
Subject: PROPOSAL (new) SOLUGH WALL
To: duckworth.donald@gmail.com

D. D. CONSTRUCTION
DERRYL DENNE
8335 Somerset Blvd
Paramount, CA 90723
[\(562\) 569-2708](tel:(562)569-2708)

Date: 03/24/15

PROPOSAL

UP TO DATE

To:
Don Duckworth

Job Location:
Sepulveda Blvd
79th & 83rd East Side
Westchester

WORK TO BE DONE

**BUILD CONCRETE SLOUGH WALL
OR CURB & MOVE SPRINKLERS**

POUR 469 LF OF SLOUGH WALL OR CURB.

- 1). FORM AND POUR (23) SECTIONS OF CONCRETE WALL
TO PREVENT DIRT & MUD RUN OFF ON TO SIDEWALK.
6" X 24" X 569' (LF CURB)
 - * THERE ARE (13) AREAS BEHIND TREES @ (8 LF) EACH
 - * THERE ARE (2) AREAS IN FRONT OF TREES @ (8 LF) EA.
 - * THERE ARE (8) OTHER AREAS 13' 13' 15' 165' 13' 77' 39' 14'
TOTAL OF 469 LF.....

NOTE : THE (13) AREAS BEHIND TREES WILL NEED TO HAVE
A DEEPER FOOTING BECAUSE IN MIDDLE OF SLOPE.

MOVE SPRINKLERS BEHIND SLOUGH WALL OR CURB.

- 2). DIG UP EXISTING SPRINKLERS & REROUTE BEHIND WALL
 - * MAY NEED TO CHANGE OUT SPRINKLER HEADS AS THEY
ARE MANY DIFFERENT KINDS ON THERE NOW..

TOTAL MATERIALS AND LABOR.....\$ 10,669.75

***Thank You For The Opportunity
To Give You This Proposal.***

---- Derryl ---